No.	Description of work	Per	Quantity
23	Supplying and fixing stone mortar and pestle	Each	10
24	Constructing sinks in bath room and kitchen with cuddapah slabs flooring on concrete bed and cement pointing, etc., complete.	,,	20
25	Honne wood eave board plain (9″×1″)	R.ft.	578
26	Providing and fixing Honne wood railings to the front verandahs with frames, vertical and cross pieces, etc., complete.	S.ft.	107
27	Chaccolate painting two coats	Sqr.	47·79
28	Providing and fixing Honne wood wall shelves with planks 1″ thick and pegs, etc., complete.	S.ft.	235
29	Supplying and fixing in cement galvanized iron pipes of 1¼′ long and 1½″ diameter for drains in bath rooms.	Each	20
30	Supplying and fixing turned wooden pegs (coat hangers) in walls.	,,	80
31	Flooring with 1½″ caddapah slabs on 3″ concrete bed and cement pointing, complete.	Sqr.	1·40
32	Supplying and fixing caddapah slabs at sides of walls inside the latrine with mortar and cement pointing to prevent the action of uric acid on walls to 2 feet height from ground.	,,	3·15
33	Wood oiling to reepers in Mangalore tiled roofing (two coats)...	,,	17·86
34	Providing and fixing zinc sheet chimneys 6″ diameter with caps on roof and with bottom planks and cement mortar bond round the same, complete.	Each	20
35	Constructing mortar bond in valleys with cement and plastering at sides, etc., complete.	R.ft.	166
36	Constructing chunam borders or binding walls over roof with brick in mortar and plastering, etc., complete (9″ x 9″).	,,	115
37	Providing small mortar bonds on roof by the side of walls, connecting the roof and the wall.	,,	100
38	Gravelling the open yard in compound and tamping complete ...	C.yd.	31
39	Supplying and fixing wooden turned finials including painting complete (big size) over hipped and gabled roof.	Each	7
40	Supplying and fixing turned wooden pendents (small size) ...	,,	20
41	Plastering with cement mortar the sills of windows and ventilators and making a drain hole in the frame.	,,	44
42	Constructing dwarf walls 9″ x 9″ with brick in mortar and cement plastering, to protect the cuddapah slab flooring in the open yard.	R.ft.	35
43	Preparing and fixing a date stone with chiseling letters, etc., complete.	Each	1

R. L. STEELE,
Executive Engineer.

KADUR DIVISION.

Dated 15th August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 8th September 1930, for constructing two quarters for Barr Officers at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees ninety only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing two quarters for Barr Officers at Chikmagalur in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be noted for each item of work.

10. Percentage quotations either below the lowest tender or sanctioned estimated amount will not be accepted.

11. The contract must not be sub-let.

12. No claims for enhanced rates will be preferred of tender and during the course of execution of work.

13. In all matters of dispute regarding quality of work, rates, etc. the decision of the Superintending Engineer, Shimoga Circle, is final and legally binding.

Approximate quantities for constructing two quarrers for Barr Officers at Chikmagalur :—

Sl. No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
1	Clearing site and levelling ground ...	L S.			
2	Earthwork excavation and filling basement ...	C.yd.	54		
3	Burnt stone in mud	C.ft.	2,212		
4	Do mortar	„	780		
5	Do in mud	„	2,100		
6	Teakwood battened door with double shutters, tower bolts, stoppers, locking arrangements, etc., complete.	S.ft.	309		
7	Teakwood battened windows big with iron bars hinged stoppers tower bolts rings in 4 halves, etc., complete.	„	69		
8	Teakwood shelves with cross battened shutters locking arrangement, etc., complete.	„	24		
9	Burnt stone slabs dressed and fixed in mortar 4½″ to 6″.	„	178		
10	Honney wood wrought and put up ...	C.ft.	64·52		
11	Teakwood eave board plain 9″ x 1″ ...	R.ft.	94		
12	Roofing with First Class Mangalore tiles on teak reepers.	Sqr.	14·96		
13	Ventilating tiles for kitchen, dining and bed rooms.	No.	12		
14	Ridge tiles set in mortar and cement pointed...	R.ft.	47		
15	Cuddapah slab filooring on 3″ concrete bed and cement pointing.	Sqr.	2·11		
16	Flooring with First Class Mangalore tiles on 3″ concrete bed and cement pointing.	„	5·29		
17	Burnt stone slab 4″ flagging, strongly on 3″ surki mortar.	S.ft.	0·32		
18	Chunam borders with chunam plastering, etc., complete.	R.ft.	52		
19	2″ drain galvanised iron pipes to lead off sullage water.	No.	1		
20	Stone jelly surki concrete 4″ U shaped with cement plastering.	R.ft.	8		
21	Slabbed V shaped drain to be fixed in stone jelly surki concrete and cement pointing and plastering, etc., complete (1½′ slabs) on either side.	„	50		
22	Tarring to woodwork imbedded in walls ...	Sqr.	3·00		
23	Plastering with mortar	„	58·53		
24	Surki plastering	„	2·20		
25	Burnt cut stone work set in mortar ...	C.ft..	7		
26	Coping over compound wall	R.ft.	122		
27	Wood oiling two coats	Sqr.	3·00		
28	Stone bench nicely dressed and fixed ...	No.	1		
29	White washing two coats	Sqr.	58·53		

L. A. H. WINCKLER,
Executive Engineer.